

Population genomics of *Digitaria insularis* from soybean areas in Brazil

Acácio Gonçalves Netto,^a Erick MG Cordeiro,^a Marcelo Nicolai,^b Saul JP de Carvalho,^c Ramiro Fernando Lopez Ovejero,^d Caio ACG Brunharo,^{e*} Maria I Zucchi^f and Pedro J Christoffoleti^a



Abstract

BACKGROUND: *Digitaria insularis* is a weed species that has gained considerable importance in Brazil's soybean production areas that rely on glyphosate-resistant cultivars. Herbicide-resistant weed populations of this species have been reported in many regions in Brazil, first in the south, followed by later reports in the north. We hypothesized that the spread of herbicide-resistant *D. insularis* is facilitated by movement of agricultural machinery from the southern regions of Brazil.

RESULTS: Population genomics revealed a weak or no genetic structure ($F_{ST} = [0; 0.16]$), moderate expected heterozygosity ($H_E = 0.15; 0.44$) and low inbreeding ($F_{IS} = [-0.1; 0.1]$) in *D. insularis* populations. Our data supported the hypothesis that herbicide resistance gene flow predominantly occurred in a south-to-north direction based on a migration analysis. We also found evidence of local adaptation of resistant populations in the northern soybean-growing regions of Brazil.

CONCLUSION: Evidence in our work suggests that gene flow of glyphosate-resistant *D. insularis* is associated with movement of agricultural machinery, although local selection pressure seems to play an important role in the evolution of herbicide resistance throughout the country. Our results suggest preventive practices such as equipment sanitation should be implemented to limit the spread of herbicide resistant *D. insularis*.

© 2021 The Authors. *Pest Management Science* published by John Wiley & Sons Ltd on behalf of Society of Chemical Industry.

Supporting information may be found in the online version of this article.

Keywords: adaptation; admixture; glyphosate resistance; herbicide resistance; sourgrass; weed genomics

1 INTRODUCTION

Widespread adoption of herbicide-resistant crops in agriculture has provided several benefits for society. For instance, more environmentally friendly compounds¹ could be adopted that also provide adequate weed control and crop selectivity. Boosting agriculture production systems is one of the pillars of sustainable intensification of agriculture, and herbicides are essential to increase crop yields.² However, the overreliance on herbicides as the primary weed management tool has selected for many herbicide-resistant weed populations worldwide.³ To date, there are 514 unique cases of herbicide-resistant weeds globally that have evolved resistance to 23 of the 26 known herbicide mechanisms of action.³

Digitaria insularis is a diploid ($2n = 36$), outcrossing,⁴ C_4 perennial weed species native to South America that propagates by seed and rhizomes and is commonly found throughout the tropical regions of South, Central, and North America. The seeds have silky hairs that aid in long-distance wind dispersal and attach to heavy machinery, whereas the rhizomes may aid dispersal following their fragmentation during agricultural practices (for example, tillage). Once plants become established, control is challenging due to the dual reproduction system this species exhibits.

D. insularis is predominant in South America's crop-growing regions, where the primary cropping system is a double-crop year of soybean–corn followed by soybean–corn. Typically, corn and soybean varieties with glyphosate resistance traits are widely adopted during both crop seasons. Overreliance on glyphosate

* Correspondence to: C ACG Brunharo, Department of Crop and Soil Science, Oregon State University, Corvallis, OR, USA. E-mail: Caio.Brunharo@oregonstate.edu

a Crop Science Department, Luiz de Queiroz College of Agriculture, University of São Paulo, Piracicaba, Brazil

b Agro do Mato Consulting, Santa Barbara D'Oeste, São Paulo, Brazil

c Federal Institute of Education, Science and Technology of the South of Minas Gerais, Machado, Minas Gerais, Brazil

d Bayer Crop Science Brazil, São Paulo, Brazil

e Department of Crop and Soil Science, Oregon State University, Corvallis, OR, USA

f Secretariat of Agriculture and Food Supply of São Paulo State, Piracicaba, Brazil

as the primary weed management tool selected for glyphosate-resistant populations of *D. insularis* in Paraguay in 2005,³ and these are believed to have dispersed to Brazil soon after their first detection given their geographical proximity.³

In 2012, most of the glyphosate-resistant populations were present in the southern states of Brazil (for example, São Paulo and Paraná). However, years later, many other glyphosate-resistant populations were identified in the central and northern regions of Brazil.⁵ Recent studies have indicated that the dispersal of *D. insularis* throughout Brazil follows routes used in the movement of machinery (mainly combines and sprayers) from southern to northern regions of the country.⁶

This research aimed to investigate population genetic structure and gene flow among glyphosate-resistant populations of *D. insularis* sampled in the most relevant soybean-growing regions in Brazil. We hypothesize that alleles associated with glyphosate resistance have a single origin in southern Brazil and have dispersed northward aided by agricultural machinery and seasonal migration to the north. Understanding the sources of initial dispersal of herbicide-resistant weed populations may help develop management practices and policies to contain herbicide resistance gene flow.

2 MATERIALS AND METHODS

2.1 Source of *D. insularis* populations

Digitaria insularis specimens were sampled from 12 soybean farms in four different states in Brazil (Fig. 1 and Table S1). For each field, mature seed heads were randomly collected from 50 plants throughout the field, sealed in a paper bag, and stored in a dry environment until further analysis. Sampling took place late in the season, near completion of the soybean growing cycle. Therefore, sampled plants are likely escapees from the weed management practices of the current growing season. Seeds were germinated in commercial potting media, transplanted to 5 × 5 cm pots, and grown in a greenhouse for initial glyphosate resistance screenings. Three plants from each population were sprayed with 960 g acid equivalent (a.e.) ha⁻¹

of glyphosate (Roundup Transorb R®) using Teejet XR11002 nozzles calibrated to deliver 200 L ha⁻¹ of herbicide mixture. The response to glyphosate was assessed visually using a 0–100% scale, where 0% represents the absence of any visual symptoms and 100% represents complete plant death. Each population was classified as susceptible (if all plants exhibited more than 80% visual injury), segregating (if at least one plant exhibited more than 80% visual injury), and resistant (if all plants exhibited less than 80% visual injury). Only three individuals per population were screened because this step was part of a much larger project to map glyphosate resistance in *D. insularis*, and space constraints prevented a greater number of replications.

2.2 DNA extraction, quality control, sample preparation and sequencing

After the conclusion of the initial glyphosate resistance screening, seeds from the original field populations were germinated (eight plants per population). Leaf tissue was collected from the youngest fully expanded leaves on 10-day-old plants and immediately frozen in liquid nitrogen and stored in a –80°C freezer until further manipulation. After tissue collection, samples were treated with 960 g a.e. ha⁻¹ of glyphosate to confirm the response to glyphosate for each individual in the populations. Glyphosate resistance status in this expanded screening agreed with the preliminary evaluation in Section 2.1.

Genomic DNA extraction was performed using the CTAB method,⁷ followed by a spectrophotometric quantification step using a NanoDrop (Thermo Scientific). A sample of DNA was digested with HindIII to assess DNA integrity by gel electrophoresis. The remainder of the sample was normalized to 30 ng µl⁻¹ and digested with the restriction enzymes PstI and MseI (New England Biolabs).

The method proposed by Elshire *et al.*⁸ was adopted to prepare the libraries for genotype by sequencing (GBS). After DNA digestion, Illumina adapters with unique barcodes were ligated to the digested DNA, followed by pooling of 96 samples and amplification by polymerase chain reaction (PCR). The library was



Figure 1. Origin of *Digitaria insularis* populations used in this study. Circles, diamonds and triangle represent glyphosate-resistant, glyphosate-susceptible and segregating, respectively.

quantified with quantitative PCR (qPCR) using the KAPA Library Quantification kit (KAPA Biosystems) following the manufacturer's recommendations. Sequencing was performed in an Illumina NextSeq 500 in a single read mode (150 bp).

2.3 Genotypes and SNP filtering

Samples were demultiplexed and processed with the process_radtags module of Stacks v.2.437,⁹ considering the recognition sites of PstI and MseI, and single-ended reads were truncated to 90 bp. The *de novo* pipeline in Stacks was adopted to first build loci *de novo* in *ustacks* using the parameters $M = 2$, $m = 3$ and $n = 2$, following the parameter optimization guidelines.^{10, 11} A catalog of loci was built with the *cstacks* module, followed by alignment of the reads to the catalog built using *sstacks*, and finally *gstacks* for genotype calling. The *populations* module filtered the dataset to keep loci that are common in at least 40% of the individuals in each population ($r = 0.4$), minor allele frequency of 5% ($-min-maf = 0.05$), and maximum observed heterozygosity of 75% ($-max-obs-het = 0.75$). Outputs were saved in genepop, vcf, and structure (.str) formats for downstream analyses.

2.4 Determining loci under selection

We used BayeScan¹² with default values to identify loci under neutral and positive selection. BayeScan uses a Markov Chain Monte Carlo method to estimate fixation indices for each population in the plant genome. A total of 20 pilot runs ($-nbp\ 20$) with a length of 5000 ($-pilot\ 5000$) were performed. We then performed a burn-in of 50 000 ($-burn\ 50\ 000$) interactions with 10 thinning intervals ($-thin\ 10$). Prior odds for the neutral model was the default value ($-pr_odds\ 10$) and posterior distribution of 0.95 as candidates for positive selection.

2.5 Genetic diversity, inbreeding coefficient and linkage disequilibrium

We used the R package adegenet¹³ to calculate the expected heterozygosity (H_E) and inbreeding coefficient (F_{IS}) based on the single nucleotide polymorphism (SNP) data set obtained. F_{IS} was calculated as $1 - (H_O/H_E)$, where H_O was the observed heterozygosity. Values near zero indicate random mating, whereas positive and negative values indicate inbreeding and outbreeding,

respectively. We determined the indices of associations, $\bar{r}_d$,¹⁴ between any pair. The lack of association between pairs of loci indicates that markers are independent, which means that there has been recombination between the markers, whereas deviation from the expected genotypic frequencies can be interpreted as linkage. We used the R package poppr¹⁵ to analyze each population independently with 1000 permutations.

2.6 Fixation index, direction and magnitude of migration, and population structure

Relative migration between pairs of populations was calculated based on the allele frequency using the R package diveRsity,¹⁶ based on the G_{ST} statistics using 10 000 permutations to infer significance.¹⁷ This method builds relative migration levels between populations, and we included two separate analyses: (a) considering all potential migration networks, and (b) considering only those that are statistically significant based on non-overlapping relative migration at the 95% confidence interval. The genetic structure was evaluated using the software ADMIXTURE v.1.22, where values of K were obtained from 1 to 15. The optimum K values were obtained using cross-validation to infer the most probable number of ancestral populations.¹⁸ Principal component analysis (PCA) was performed with the R package adegenet¹³ and ade4.¹⁹ We performed independent PCA analyses with SNP exhibiting positive and neutral selection.

3 RESULTS

In total, 4245 SNPs were generated using Stacks and were subsequently used for the population genomics analysis in this study. Considerable variation in H_E was observed among the sampled populations (Fig. 2). The populations with the highest and lowest H_E values were MTDIS and MTDIR, respectively. Originating from Paraná state, PRDVR exhibited the lowest H_E value. F_{IS} values also ranged widely (Fig. 3). Four populations from distinct locations had negative F_{IS} values (populations below red, dashed line), whereas six locations had positive F_{IS} values. Two populations had F_{IS} values equal to zero.

Average F_{ST} values varied from 0 to 0.16, indicating low to moderate differentiation (Table 1). Population MABAI, from northern




Figure 2. Observed heterozygosity (H_E) for 12 *Digitaria insularis* populations from Brazil. Solid black circles represent mean values, whereas bars represent 95% confidence intervals. For population origins and labels, see Figs 1 and S1.




Figure 3. Inbreeding coefficient (F_{IS}) calculated for 12 *Digitaria insularis* populations from Brazil. Solid black circles represent mean values, whereas bars represent 95% confidence intervals. The dashed red line represents the zero F_{IS} value. For population origins and labels, see Figs 1 and S1.

Table 1. Pairwise fixation index (F_{ST}) (upper) and P -values (lower) for 12 *Digitaria insularis* populations from Brazil

	MABAI*	MTDIR	MTDIS	MTLVR	MTLRR	MTNMS	MTSOS	MTSPR	MTSRS	PRDVR	PRPGR	TOPAR
MABAI		−0.46	0.05	0.08	0.07	0.07	0.16	0.05	0.11	−0.06	0.08	−0.02
MTDIR	1.00		−0.99	−0.63	−0.46	−0.70	−0.45	−0.53	−0.67	−0.61	−0.69	−0.89
MTDIS	0.01	1.00		0.02	0.05	−0.03	−0.08	−0.10	−0.06	−0.15	−0.01	0.04
MTLVR	0.00	1.00	0.02		0.10	− 0.01	0.07	0.06	−0.07	0.01	0.11	0.06
MTLRR	0.00	1.00	0.00	0.00		0.07	0.10	−0.03	0.02	−0.07	0.05	0.07
MTNMS	0.00	1.00	0.44	0.06	0.00		−0.02	−0.05	−0.06	−0.10	0.02	0.03
MTSOS	0.00	1.00	0.95	0.00	0.00	0.18		0.06	−0.06	0.07	0.03	0.07
MTSPR	0.00	1.00	0.95	0.00	0.43	0.51	0.01		0.01	−0.05	−0.03	−0.12
MTSRS	0.00	1.00	0.87	0.76	0.02	0.72	0.63	0.07		−0.06	−0.02	0.01
PRDVR	0.64	1.00	0.99	0.02	0.82	0.94	0.01	0.41	0.51		−0.04	−0.14
PRPGR	0.00	1.00	0.10	0.00	0.00	0.00	0.00	0.32	0.19	0.52		0.05
TOPAR	0.20	1.00	0.00	0.00	0.00	0.01	0.00	0.96	0.06	1.00	0.00	

*Values in bold represent F_{ST} values different than zero ($P < 0.05$). For population origins, see Fig. S1.

Brazil (Maranhão state), had the highest F_{ST} value (0.16) compared with population MTSOS. Low genetic structure was observed for most pairwise comparisons indicating high gene flow. Unrooted phylogenetic analysis (Fig. S1) supports F_{ST} analysis because the radial layout of the tree indicates a close genetic relationship among the collected *D. insularis* locations.

The $\bar{r}_d$ coefficients were significant ($P < 0.001$) in 7 of the 12 sampled locations, indicating disequilibrium between markers in those locations (Table 2). In this test, the null hypothesis is that no linkage exists between markers, and consequently sexual reproduction is predominant. Samples from Paraná (PRDVR and PRPGR), Maranhão (MABAI) and Mato Grosso state (MTLVR and MTSPR) seem to be in equilibrium, whereas MTDIR, MTDIS, MTLRR, MTNMS, MTSOS and MTSRS (from Mato Grosso state), as well as TOPAR (from Tocantins state) are in disequilibrium (Table 2).

An asymmetric direction of dispersal was observed in *D. insularis*, driven primarily by populations PRDVR and MTDIR (Fig. 4). Population PRDVR contributed most to the number of migrants and exhibited the largest impact on the population

Table 2. Index of association in 12 *Digitaria insularis* populations in Brazil

Sample ID*	Indices of association ($\bar{r}_d$)	P -value
MABAI	0.0775	1.000
MTDIR	0.0833	0.001
MTDIS	0.0289	0.001
MTLVR	0.0415	1.000
MTLRR	0.0602	0.001
MTNMS	0.0356	0.001
MTSOS	0.0755	0.001
MTSPR	0.0666	1.000
MTSRS	0.0871	0.001
PRDVR	0.0356	1.000
PRPGR	0.0575	0.496
TOPAR	0.0175	0.001

*For population origins, see Fig. S1.




Figure 4. Direction of gene flow and magnitude of migration in *Digitaria insularis* populations from Brazil using G_{ST} . Arrows indicate the direction of gene flow; numbers represent the relative coefficient of migration. (A) All potential migration routes. (B) Migration routes after a threshold filter is implemented of 0.05 probability.

dynamics of this weed in the sampled populations from Brazil. Population MTDIR was the second most influential population and contributed to alleles in Mato Grosso, Paraná and Tocantins states. Other populations showed less involvement in the dispersal of alleles throughout the country. Interestingly, of the southern populations, only PRDVR showed patterns of migration to other *D. insularis* populations; by contrast PRPGR did not show significant migration networks (Fig. 4(B)). If our hypothesis is correct that gene flow in *D. insularis* is primarily mediated by the movement of agricultural machinery, then local agricultural practices (for example, tillage versus no-tillage, cropping system,

rotation sequence), as well as farm ownership will play an important role in the direction of gene flow.

In total, 1134 SNPs were putatively neutral, and 687 had evidence of positive selection, according to BayeScan analysis. ADMIXTURE analysis using the 1134 neutral SNPs indicated that $K = 3$ was the most appropriate number of clusters given the populations under study (Fig. 5(A)) based on the cross-validation test. Limited population structure was observed in most collected regions, except MABAI, PRDVR and MTLVR.

When we used only SNPs under positive selection, a clearer clustering pattern could be observed. Structure analyses using




Figure 5. ADMIXTURE and principal component analysis (PCA) of 12 *Digitaria insularis* populations. ADMIXTURE analysis was performed using 1134 neutral single nucleotide polymorphisms (SNPs) with $K = 3$ (A), and 687 SNPs under positive selection and $K = 5$ (B). PCA with neutral SNPs (C) and SNPs under positive selection (D) were also performed. Populations were divided into five groups (G1–G5) for the analyses with SNPs under positive selection.

markers putatively under selection revealed clustering patterns compatible with geographical location and resistance status ($K = 5$). Using ADMIXTURE results on markers putatively under positive selection, we proposed grouping labels to aid visualization: G1, MTLRR and PRPGR (blue); G2, MABAI (purple); G3, MTLVR (pink); G4, MTNMS, MTSOS and MTSRS (green); and G5, MTDIR, MTSPR, PRDVR and TOPAR (orange). Locations sharing the same resistance status within the same broad geographical location tended to share more ancestry and be more closely grouped. A similar pattern was observed in the susceptible samples.

PCA broadly supports the conclusions of the ADMIXTURE analysis showing no structure when the neutral markers were used but more evident clustering when positive markers were used (Fig. 5 (C),(D)). The three groups containing resistant individuals (G1, G3 and G5) were separated from one another. PC1 explained a significant variation (13.74 to 31.86%) as did PC2 (6.87 to 10.71%) for both SNP data sets. This pattern is further corroborated by phylogenetic and F_{ST} analyses.

4 DISCUSSION

Digitaria insularis is considered one of the most troublesome weed species in Brazil's soybean cropping systems, particularly aggravated by the widespread evolution of glyphosate-resistant populations. Currently, two hypotheses can explain the rapid pace with which resistance has evolved over an extensive geographic range. The first hypothesis suggests that resistance evolved once in the south, where it was first reported in Paraguay, and then spread northwards. The second hypothesis suggests that resistance to glyphosate evolved multiple times. Our data indicate that one of the main features of *D. insularis* population dynamics is the high degree of gene flow between areas, which makes the first hypothesis more likely. However, using only putative markers under positive selection, three different clusters containing resistant samples could be identified, suggesting a different pattern of evolution in the various regions.

ADMIXTURE analysis reveals a moderate genetic structure between the two southern locations (PRDVR and PRPGR), but both locations in the south seem to be well connected to Mato Grosso's central locations. These results may support the hypothesis that movement of agricultural machinery could have assisted the spread of *D. insularis* to the north. In general, soybean sowing occurs earlier in southern regions than in the north due to precipitation patterns. Therefore, machinery becomes available for use in Brazil's northern regions later in the season after operations in the south are finished. This sharing of agricultural equipment is only possible because many farmers own land in both locations and because third-party companies in different regions may perform custom farming operations. Preventing weed propagule movement is one of the pillars of integrated weed management, and sanitizing machinery is crucial.^{20, 21} Our results support the notion that long-distance spread of *D. insularis* followed the direction of the agricultural machinery movement and could be used to better inform farmers and agronomists of the importance of sanitizing equipment.

Considering the timeline over which glyphosate resistance has developed in South America, we can relate our results to historical facts. Population PRDVR was collected from south Paraná state, near the border with Paraguay, where the first glyphosate-resistant *D. insularis* was reported. Unfortunately, we did not include the Paraguayan population in our analysis, but the high

gene flow observed in this study might suggest that resistance genes have spread across the borders. Movement of *D. insularis* propagules between countries is not unexpected because many farmers own land on both sides of the border.

Overall, no clear relation between the observed H_E (genetic diversity) and glyphosate resistance status or geographic region can be drawn. For instance, MTDIR exhibited the lowest H_E , whereas MTLRR exhibited one of the largest values. These results indicated that local *D. insularis* populations might be involved in the evolutionary rescue of glyphosate-resistant populations, increasing H_E after the initial bottleneck caused by the herbicide.²² This is because once a glyphosate-resistant population is introduced to a new location, genetic diversity is limited because of the few individuals that founded the population. However, because of the outcrossing mating system of *D. insularis*, genetic diversity may be restored by gene flow from other localities. This may also enable populations to adapt more rapidly to the management practices other crop production systems.²³ Our H_E results indicate that the magnitude of *D. insularis* dispersion is greater than observed in the outcrossing weed species *Alopecurus myosuroides*, where it was found that H_E varied from 0.09 to 0.14, approximately, in populations exhibiting different patterns of herbicide resistance.²⁴ Similarly, the H_E value of *D. insularis* is larger than that of the predominantly self-pollinated weed species *Brum tectorum* which exhibited a mean H_E of 0.2.²⁵ The higher H_E levels in *D. insularis* further support the idea that admixture plays an important role in maintaining genetic diversity in populations.

Estimates of the inbreeding coefficient (F_{IS}) indicated that populations exhibited limited inbreeding because these values ranged between -0.1 and 0.1 , suggesting the *D. insularis* populations studied maintained their outcrossing behavior. The observed low inbreeding coefficients could indicate the limited ability of *D. insularis* to self-pollinate under local environmental conditions. For example, in *Lolium multiflorum*, an outcrossing weed species, F_{IS} ranged from 0.374 to 0.475 for 14 glyphosate-resistant populations from California.²⁶ Asexual reproduction in populations of *D. insularis* was particularly important for 7 of the 12 populations studied, according to the index of association analysis (Table 2), corroborating the F_{IS} results.

BayeScan analysis identified more than 1000 loci under selection. It is difficult to infer whether the SNPs are physically close because of the absence of a reference genome for this species, although there are ongoing efforts to make this resource available.²⁷ Therefore, it is possible that a few regions of the genome are under selection. Furthermore, BayeScan analysis may also identify selection pressure from other agents, such as use of other herbicides, management practices and climate conditions.

Populations were collected in glyphosate-resistant soybean areas, where multiple herbicide applications were likely made before sampling. To further eliminate glyphosate-susceptible genotypes, we applied a lethal glyphosate dose to individuals to ensure the genotype-by-sequencing study was conducted with known resistant and susceptible individuals. Interestingly, at least two different genetic clusters of resistance are apparent when the resistant populations are considered. For instance, resistant population PRPGR exhibits, at $K = 3$, individuals that are entirely from the blue and purple backgrounds. Because they are all glyphosate resistant, the resistance alleles are both found in the blue and purple genetic backgrounds. This suggests that glyphosate resistance might interplay with different regional dynamics, including multiple mutations in different genetic backgrounds that likely evolved multiple times independently. More research

needs to be conducted to identify whether these mutations are similar among populations. The mechanisms of glyphosate resistance in *D. insularis* have not been completely elucidated. Glyphosate-resistant *D. insularis* populations are characterized by not exhibiting mutations in the gene that encoded glyphosate's target enzyme; however, they may prevent the herbicide from systemically moving in the plant.^{28,29} Conversely, other resistant populations do not exhibit target site mutations or reduced herbicide translocation,²⁹ indicating non-target-site resistance mechanisms are predominant in *D. insularis* and will require more integrated 'omics' approaches to improve our understanding.³⁰

5 CONCLUSION

Here, we uncover important aspects of *D. insularis* population dynamics in Brazilian soybean fields. Outcrossing populations spread their genes across a large range likely aided by heavy machinery. *D. insularis* populations are under strong positive selection associated with herbicide usage; however, clustering patterns suggest subtle differences in the process of resistance evolution in different areas. Future research should address two main follow-up questions. What are the mechanisms of resistance in these populations? Moreover, did glyphosate resistance in the *D. insularis* populations studied here evolve the same resistance mechanisms (but in different genetic backgrounds)? Answering these questions will help weed scientists develop better predictive models and understand how selection pressure by herbicides shapes weed populations and the best management practices to slow the evolution of herbicide resistance.³¹

ACKNOWLEDGMENTS

AGN would like to thank National Council of Technological and Scientific Development – CNPq – for the PhD stipend provided, the Genetics Department at ESALQ/USP, and the Institute of Biology, State University of Campinas for assistance with the analysis. We thank Bayer Crop Science for funding this work. The graphical abstract was created with Biorender (Biorender.com).

SUPPORTING INFORMATION

Supporting information may be found in the online version of this article.

REFERENCES

- Kniss AR, Long-term trends in the intensity and relative toxicity of herbicide use. *Nat Commun* **8**:1–7 (2017).
- Pretty J, Intensification for redesigned and sustainable agricultural systems. *Science* **362**:1–7 (2018).
- Heap I, The International Survey of Herbicide Resistant Weeds. Available: www.weedscience.org [16 May 2021].
- Martins JF, Barroso AAM, Carvalho LB, Cesarin AE, Amaral CL, Nepomuceno MP *et al.*, Plant growth and genetic polymorphism in glyphosate-resistant sourgrass (*Digitaria insularis* L. Fedde). *Austr J Crop Sci* **10**:1466–1473 (2016). <https://doi.org/10.21475/ajcs.2016.10.10.p7761>.
- De Carvalho LB, Cruz-Hipolito H, González-Torralva F, da Costa Aguiar Alves PL, Christoffoleti PJ and De Prado R, Detection of sourgrass (*Digitaria insularis*) biotypes resistant to glyphosate in Brazil. *Weed Sci* **59**:171–176 (2011). <https://doi.org/10.1614/WS-D-10-00113.1>.
- Lopez Ovejero RF, Takano HK, Nicolai M, Ferreira A, Melo MSC, Cavenaghi AL *et al.*, Frequency and dispersal of glyphosate-resistant sourgrass (*Digitaria insularis*) populations across Brazilian agricultural production areas. *Weed Sci* **65**:285–294 (2017). <https://doi.org/10.1017/wsc.2016.31>.
- Doyle JF and Doyle JL, A rapid DNA isolation procedure for small quantities of fresh leaf tissue. *Phytochem Bull* **19**:11–15 (1987).
- Elshire RJ, Glaubitz JC, Sun Q, Poland JA, Kawamoto K, Buckler ES *et al.*, A robust, simple genotype-by-sequencing (GBS) approach for high diversity species. *PLoS One* **6**:1–10 (2011). <https://doi.org/10.1371/journal.pone.0019379>.
- Rochette NC, Rivera-Colón AG and Catchen JM, Stacks 2: analytical methods for paired-end sequencing improve RADseq-based population genomics. *Mol Ecol* **28**:4737–4754 (2019).
- Rochette NC and Catchen JM, Deriving genotypes from RAD-seq short-read data using stacks. *Nat Protoc* **12**:2640–2659 (2017).
- Paris JR, Stevens JR and Catchen JM, Lost in parameter space: a road map for stacks. *Methods Ecol Evol* **8**:1360–1373 (2017). <https://doi.org/10.1111/2041-210X.12775>.
- Foll M and Gaggiotti O, A genome-scan method to identify selected loci appropriate for both dominant and codominant markers: a Bayesian perspective. *Genetics* **180**:977–993 (2008).
- Jombart T, ADEGENET: a R package for the multivariate analysis of genetic markers. *Bioinformatics* **24**:1403–1405 (2008).
- Agapow P-M and Burt A, Indices of multilocus linkage disequilibrium. *Mol Ecol Notes* **1**:101–102 (2001). <https://doi.org/10.1046/j.1471-8278.2000.00014.x>.
- Kamvar ZN, Tabima JF and Grünwald NJ, Poppr: an R package for genetic analysis of populations with clonal, partially clonal, and/or sexual reproduction. *PeerJ* **2**:e281 (2014).
- Keenan K, McGinnity P, Cross TF, Crozier WW and Prodöhl PA, diversity: an R package for the estimation and exploration of population genetics parameters and their associated errors. *Methods Ecol Evol* **4**:782–788 (2013). <https://doi.org/10.1111/2041-210X.12067>.
- Nei M, Analysis of gene diversity in subdivided populations. *Proc Natl Acad Sci USA* **70**:3321–3323 (1973).
- Alexander DH, Novembre J and Lange K, Fast model-based estimation of ancestry in unrelated individuals. *Genome Res* **19**:1655–1664 (2009).
- Dray S and Dufour A-B, The ade4 package: implementing the duality diagram for ecologists. *J Stat Software* **22**:1–20 (2007). <https://doi.org/10.18637/jss.v022.i04>.
- Takano HK, Melo MSC, Ovejero RFL, Westra PH, Gaines TA and Dayan FE, Trp202Cys mutation evolves in *Digitaria insularis* with cross-resistance to ACCase inhibitors. *Pestic Biochem Physiol* **164**:1–6 (2020).
- Beckie HJ and Harker KN, Our top 10 herbicide-resistant weed management practices. *Pest Manag Sci* **73**:1045–1052 (2017).
- Carlson SM, Cunningham CJ and Westley PAH, Evolutionary rescue in a changing world. *Trends Ecol Evol* **29**:521–530 (2014).
- Matzrafi M, Preston C and Brunharo CA, Review: evolutionary drivers of agricultural adaptation in *Lolium* spp. *Pest Manag Sci* **77**:2209–2218 (2021).
- Dixon A, Comont D, Slavov GT and Neve P, Population genomics of selectively neutral genetic structure and herbicide resistance in UK populations of *Alopecurus myosuroides*. *Pest Manag Sci* **77**:1520–1529 (2021).
- Lawrence NC, Hauvermale AL, Dhirra A and Burke IC, Population structure and genetic diversity of *Bromus tectorum* within the small grain production region of the Pacific northwest. *Ecol Evol* **7**:8316–8328 (2017).
- Karn E and Jasieniuk M, Genetic diversity and structure of *Lolium perenne* ssp. *multiflorum* in California vineyards and orchards indicate potential for spread of herbicide resistance via gene flow. *Evol Appl* **10**:616–629 (2017).
- Ravet K, Patterson EL, Krahmer H, Hamouzova K, Fan L, Jasieniuk M *et al.*, The power and potential of genomics in weed biology and management. *Pest Manag Sci* **74**:2216–2225 (2018). <https://doi.org/10.1002/ps.5048>.
- Melo MSC, Rocha LJFN, Brunharo CACG, Nicolai M, Tornisiello VL, Nissen SJ *et al.*, Sourgrass resistance mechanism to the herbicide glyphosate. *Adv Weed Sci* **37**:e019185746 (2019). <https://doi.org/10.1590/S0100-83582019370100033>.
- Suzukawa AK, Bobadilla LK, Mallory-Smith C and Brunharo CACG, Non-target-site resistance in *Lolium* spp. globally: a review. *Front Plant Sci* **11**:609209 (2020).
- Gazola T, Bianchi L, Dias MF, Carbonari CA and Velini ED, Metabolic profiling of glyphosate-resistant sourgrass (*Digitaria insularis*). *Weed Technol* **34**:748–755 (2020). <https://doi.org/10.1017/wet.2020.31>.
- Owen MDK, Beckie HJ, Leeson JY, Norsworthy JK and Steckel LE, Integrated pest management and weed management in the United States and Canada. *Pest Manag Sci* **71**:357–376 (2015).